

**BUREAU OF BROADCAST SERVICES**  
**4<sup>TH</sup> Floor, Media Center Building,**  
**Visayas Avenue, Quezon City**

**CANVASS FORM**

Date: \_\_\_\_\_

JO Number: \_\_\_\_\_

2020-07-0032

Gentlemen: Please quote your government price/s for the article/s listed hereunder:

Item No.	Qty	Unit	Articles	Approved ABC	Amount
1	1	Lot	<p><b>RECONDUCTORING OF OVERHEAD FEEDER LINES WITH TWO (2) CONCRETE POLES AND ACCESSORIES IN RADYO PILIPINAS MARULAS, VALENZUELA</b></p> <p>Supply of materials, labor, technical supervision, testing equipment and consumable material including the following scope necessary for the energization of the above project.</p> <p><b>SCOPE OF WORK</b></p> <p><b>A. GENERAL REQUIREMENTS</b></p> <ul style="list-style-type: none"> <li>• Mobilization / Demobilization</li> <li>• Temporary Facilities</li> <li>• Site Supervision / Administration</li> <li>• Bonds and Insurances</li> <li>• Assistance in securing of Certificate of Electrical Inspection</li> <li>• As-built / Engineering &amp; Design</li> <li>• Safety Protocols (COVID test, etc.)</li> </ul> <p><b>B. ELECTRICAL REQUIRMENTS</b></p> <p><b>1. POLE # 1</b></p> <p><b>a. POLE</b>  <i>1 pc. Concrete Pole, 9.5M ht.-CL 5</i></p> <p><b>b. SECONDARY ASSEMBLY</b>  <i>3 pcs. Spool Insulator (White)</i>  <i>3 pcs. Tie Wire for Copper</i>  <i>1pc. Secondary Rack 3 – Spool</i>  <i>2 pcs. Bolt, Machine, 16mmØ x 50mm long, HDG</i>  <i>2pcs. Pole Clamp</i>  <i>1 Lot Consumables</i></p> <p><b>c. TRUSS GUY ASSEMBLY</b>  <i>4 pcs. Eye, Thimble HGS, Hot-Dip Galvanized, 6350KG Ultimate Strength</i>  <i>8 pcs. Bolt, Machine, 16mm x 350</i>  <i>4 pcs Bolt, Machine, 19mmØ x 55</i>  <i>4 pcs. Washer, Square, for 16mmØ Bolt</i>  <i>4 pcs. Angle Arm 1500mmØ, Steel Hot-Dip Galvanized</i>  <i>12 pcs. Strain Insulator, ANSI CL 54-2, porcelain</i>  <i>16 pcs. Strain Insulator clevis, steel, HDG, 5000kg. Ultimate strength</i>  <i>4 pcs. Washer, pipe, 25mmØx19</i>  <i>8 pcs. Clamp Guy, Three Bolt Type</i>  <i>4 pcs. Bolt, Machine, 12mmØ x 40mm long</i>  <i>4 pcs. Clamp, pole, 475 mm dia.</i>  <i>4 pcs. Brace, Angle; Steel; Hot-Dip Galvanized; Size 6mm x 50mm x 50mm x 1500mm Long; For Use on Truss Guy Construction</i>  <i>4pcs. Bolt, Machine, 16mmØ x 50mm long, HDG</i>  <i>1 Lot Consumables</i></p> <p><b>d. ANCHOR ASSEMBLY</b>  <i>1 pc. Anchor Rod Twin Eye, 19 x 2400</i>  <i>1 pc. Anchor Block</i>  <i>2 pcs. Guy Marker</i>  <i>2 pcs. Tie Wire For Aluminum</i></p> <p><b>e. POLE GROUNDING(GP203)</b>  <i>1 pc. Connector, solderless for #2 CU Copper</i>  <i>14 lm. #2AWG Bare Copper Wire, Stranded</i></p>	P896,000.00	

		<p style="text-align: center;"><i>1 lot Consumables</i></p> <p><b>2. <u>POLE # 2</u></b></p> <p><b>a. <u>POLE</u></b>  <i>1 pc. Concrete Pole, 9.5M ht.-CL 5</i></p> <p><b>b. <u>SECONDARY ASSEMBLY</u></b>  <i>6 pcs. Spool Insulator (White)</i>  <i>6 pcs. Clamp Guy, Three Bolt Type</i>  <i>3 pcs. Connector, solderless for #4/0 Insulated Copper</i>  <i>2pc. Secondary Rack 3 – Spool</i>  <i>4 pcs. Bolt, Machine, 16mmØ x 50mm long, HDG</i>  <i>3 pcs. Solderless connector,#4/0</i>  <i>1 Lot Consumables</i></p> <p><b>c. <u>POLE GROUNDING(GP203)</u></b>  <i>1 pc. Connector, solderless for #2 CU Copper</i>  <i>19 lm. #2AWG Bare Copper Wire, Stranded</i>  <i>1 lot Consumables</i></p> <p><b>d. <u>OTHER MATERIALS</u></b>  <i>6 pcs. Solderless connector,#4/0</i></p> <p><b>e. <u>WIRES AND CABLES</u></b>  <i>180 lm. #4/0 AWG Insulate copper (Sec. wire)</i>  <i>14 lm. Guy wire 9.5mmØ (3/8")</i>  <i>1 lot Consumables</i></p> <p><b>f. <u>TESTING AND COMMISSIONING</u></b>  <i>1 Lot – Testing of WIRES and CABLES</i></p> <p><b>g. <u>DELIVERY AND UNLOADING OF POLES</u></b>  <i>1 Lot - Truck</i></p> <p><b>h. <u>EQUIPMENT RENTAL</u></b>  <i>3 days Boom Truck</i>  <i>2 days Crane Truck</i>  <i>3 days Basket Truck</i></p> <p><b>Warranty:</b>  Workmanship:  Three (3) months from the date of energization which excludes consumable materials such as cables, power fuse, arrester.  <b>X-X-X-X-X-X-X-X-X-X-X-X-X-X-X-X-X-X-X</b></p>		
--	--	---	--	--

Please submit your quotation \_\_\_\_\_ days after receipt of this form.

Very truly yours,

**JUDITH A. TRABALLO**

Canvasser

**BENJAMIN REUEL R. ORTIGUERO, JR.**

Chief, Procurement Service

The above price/s and /or quotation/s for the article/s you wish to purchase/repair is/are available within \_\_\_\_\_ days from the date of quotation.

**AUTHORIZED SIGNATURE**

Date quoted: \_\_\_\_\_

Price Valid For: \_\_\_\_\_

Terms: \_\_\_\_\_