

**BUREAU OF BROADCAST SERVICES**  
**4<sup>TH</sup> Floor, Media Center Building,**  
**Visayas Avenue, Quezon City**

**CANVASS FORM**

Date: \_\_\_\_\_

JO Number: 2021-05-0057

Gentlemen: Please quote your government price/s for the article/s listed hereunder:

Item No.	Qty	Unit	Articles	Approved Total ABC	Amount
1	1	lot	<b>Renovation of FM1 &amp; FM2 Transmitter Room</b>	<b>P416,556.58</b>	
			<b>Scope of Work:</b> <b>A. General Requirements:</b> <ul style="list-style-type: none"> <li>• Mobilization / Demobilization</li> <li>• Temporary Facilities</li> <li>• Site Supervision/Administration</li> <li>• Provide all labor, materials, tools, equipment, and services to renovate FM1 &amp; FM2 Transmitter Room.</li> </ul> <b>B. Material Requirements:</b> Civil and Architectural Works: <i>Floor Finishes</i> 5.45 sq.m. 20 x 20 cm ceramic floor tiles (Common C.R.) 1 lot Plain cement existing floor repair and retouch  <i>Wall Finishes</i> 14.90 sq.m. 4.5mm thk ficem board on metal stud frame double wall 1 lot 4.5mm thk ficem board on metal stud frame single wall 17.45 sq.m. 20 x 20 cm ceramic wall tiles (Common C.R.) 1 lot Plain cement plaster and retouch 10.80 Lm. Corner plastering  <i>Ceiling Finishes</i> 37.45 sq.m. 4.5mm thk ficem board on metal furring frame  <i>Door and Jambs</i> 2 sets 0.90 x 2.10m Wood flush swing door 2 sets 0.80 x 2.10m 45mm thk metal flush door G.A #18, G.I for G.A # 16, G.I sheet single rabbet jamb with accessories  <i>Carpentry Works</i> 1 lot Overhead storage  <i>Door and Hardware</i> 3 sets Lockset door faultless brand 1 pc. Barrel bolt 4 pairs Door hinges 3 1/2" x 3 1/2" stainless bearing type 1 pc. Foot bolt lock 1 lot Hardware/accessories  <i>Roofing Works</i> 1 lot Repair of lower roof/canopy 1 lot Repair of fascia board and steel frame 1 lot Replacement of end flashing 1 lot Repair of main roof  <i>Thermal and Moisture Protection</i> 1 lot Exterior walls (Cementitious waterproofing) 1 lot Main roof and lower roof (Roof guard waterproofing ) <i>Painting Works</i> 2 pails Permacoat flat latex paint boysen 2 pails Permacoat semi-gloss paint finish boysen 5 liters Assorted acri color 1 gal. Concrete neutralizer 2 bags Skimcoat 1 bag Boral 7 gals. Epoxy primer paint and epoxy enamel top coat (Floor fin.) 1 gal. Epoxy reducer 2 gals. Quick dry enamel paint boysen 1 gal. Lacquer thinner 1 gal. Paint thinner		



