

CANVASS FORM

Date: _____

PR Number: 2024-04-0140

2024-04-0145

Item No.	Qty	Unit	Articles	Approved Total ABC	Amount
1	1	Lot	Airconditioners, with Delivery and Installation Included	P415,000.00	
	1	unit	7.5 TR Split Type Floor Mounted ACU (1 Year Warranty) Specification: Cooling Capacity (kJ/hr) – 94,950 Rated Power – 9,300 Watts Rated Current – 25.4 Amp. EER (kJ/hW) – 10.21 Noise Level (low) – 60dB(A) Air Flow Volume (Hi) – 3,900 m ³ /h Pipe Size (Liquid/Gas) – 5/8" & 1 1/8" Volt/Hz/Phase – 230 Volts, 60 Hz, 3 phase Refrigerant – R410A Max Refrigerant Pipe Length – 30m	P270,000.00	
	1	unit	5.0 TR Split Type Floor Mounted ACU (1 Year Warranty) Specification: Cooling Capacity (kJ/hr) – 63,300 Rated Power – 6,500 Watts Rated Current – 19.0 Amp. EER (kJ/hW) – 9.74 Noise Level (low) – 52dB(A) Air Flow Volume (Hi/Med/Low) – 1,567 m ³ /h Pipe Size (Liquid/Gas) – 1/2" & 7/8" Volt/Hz/Phase – 230 Volts, 60 Hz, 3 phase Refrigerant – R410A Max Refrigerant Pipe Length – 30m	P145,000.00	
			Scope of Works for both Units Includes: <ul style="list-style-type: none"> ➤ Supply of labor and materials such as copper tubes, rubber insulation, THHN type electrical control wires, circuit breaker, flexible orange for control (indoor), pvc pipe for drain line, and fabrication and installation of brackets ➤ Supply water-tight flexible conduit for outdoor unit electrical supply and controls ➤ Supply of consumable items such as Freon Gas, Nitrogen Gas, Oxy-acetylene, and welding materials ➤ Leak testing and vacuuming ➤ Technical supervision, start-up and commissioning ➤ Dismantling and hauling of existing ACU unit x-x Please email this form to: pbs.bbs.procurement@gmail.com or fax to (02)8920-4353		

Very truly yours,

EMMANUEL CEDRIC M. ONTONG
Chief, Procurement Service

AUTHORIZED SIGNATURE

Price Valid For:

Terms: